

Proposed Mixed-Density Condominium Residential Development  
Millford Development Limited • Town of Newmarket

---

## **Functional Servicing and Stormwater Management Report**

March 2011  
Rev. March 2021  
MAEL Reference 99-598



**FUNCTIONAL SERVICING AND STORMWATER MANAGEMENT  
REPORT  
(Stage 1-OPA + ZBA)**

**Proposed Condominium Residential Development  
Town of Newmarket**

**Milliford Development Limited.**

**March 2011**

**Rev. March 2021**

MAEL Project No: 99-958

**MASONGSONG ASSOCIATES ENGINEERING LIMITED**

7800 Kennedy Road, Unit 201

Markham, Ontario, L3R 2C7

T: (905) 944-0162 / F: (905) 944-0165

## TABLE OF CONTENTS

1	INTRODUCTION .....	3
1.1	Objectives and Location .....	3
1.2	Existing Site Description .....	4
1.2.1	Topography .....	4
1.3	Proposed Development Plan .....	4
2	Site Grading .....	6
3	WATER SERVICING .....	7
3.1	Existing Water Servicing .....	7
3.2	Proposed Water Servicing.....	7
3.3	Proposed Water Demands.....	7
4	SANITARY SERVICING .....	10
4.1	Proposed Sanitary Servicing.....	10
4.2	Sanitary Sewage Flows Estimates .....	10
5	STORM DRAINAGE AND STORMWATER MANAGEMENT .....	12
5.1	Existing Storm Servicing .....	12
5.2	Proposed Post-development conditions.....	13
5.2.1	Water Balance.....	13
5.2.2	Allowable Peak Flow- Pre-Development .....	16
5.2.3	Post-development Discharge .....	18
5.2.4	Stormwater Quality Control.....	20
5.2.4.1	TSS removal .....	20
5.2.4.2	TOTAL PHOSPHOROUS .....	21
6	EROSION AND SEDIMENT CONTROL .....	23
7	CONCLUSIONS AND SUMMARY RECOMMENDATIONS.....	24

## APPENDICES

- Appendix A:** Site Plan, and Survey
- Appendix B:** Figures 2 to 8 and city drawings
- Appendix C:** Design sheet, Waterman Tables, preliminary sizing of OGS

**Appendix D:** Geotechnical Letter of Opinion, dated September 2020, prepared by Soil Engineers Ltd.  
Historical documents for western sanitary subtrunk

## 1 INTRODUCTION


### 1.1 Objectives and Location

Masongsong Associates Engineering Limited has been retained by Millford Development Limited, to prepare this Functional Servicing and Stormwater Management report for a proposed condominium residential development comprising 53 Townhouse units, 20 back-to-back town houses units, and 1 triplex in support of a rezoning application.

This report addresses conceptual design for zoning whereas detailed design shall be submitted during site plan approval.

The overall developable land of approximately 2.03Ha (5.02 acres) fronts onto Eagle Street, east of Yonge Street, between Dixon Blvd and Donlin Ave. It is bounded to the north by Western Creek which is tributary to the East Holland River in the Town of Newmarket; to the west by existing commercial/industrial sites and to the east by residential development and auto repair facility. Figure 1 below illustrates the location of the proposed development.

**Figure 1** illustrates the location of the proposed development.



This report outlines the criteria and standards that have been implemented in the design of the site and will demonstrate how the site fits within the framework of existing receiving systems located along Eagle Street. This report will also describe the stormwater management controls proposed within the subject site to meet the established outflow targets outlined in current Town of Newmarket Design Standards and Criteria

## **1.2 Existing Site Description**

### **1.2.1 Topography**

The existing topographic survey indicates that the lands generally slope from the southwest to the northeast, with a 10.5m grade differential, ranging from a height of 267.0m on the table land, to a low of 256.5m at the base of the valley feature. The peak elevation is located on the southwest corner near Eagle Street, while the low elevations are on the opposite corner at the top of bank as established by Lake Simcoe Regional Conservation Authority (LSRCA) in April 2009 and confirmed in May 2012. Refer to LSRCA letter enclosed in Appendix D.

A topographic and legal survey plan prepared by Young and Young Surveying Inc. are included in Appendix A as Drawings TP1 and TP2.

The northerly portion of the site is bounded by Western Creek which is a tributary of the East Holland River. The tributary runs in a north-easterly direction and traverses the north side of the subject lands. As mentioned in the *Tree Inventory Report* (C.V. Bentley, 2007), remnants of planted areas of trees and shrubs suggest that the property was previously a residence or farm. Open areas, indicating old fields or other disturbed areas, are being colonized naturally by invasive or early successional species. There are no natural areas of native forest observed in the proposed area of development.

Field studies have been updated in 2020 and a new Environmental Impact Statement has been completed by GeoProcess Research Associates, dated March 2021.

A 6m wide buffer zone was established by LSRCA on April 16, 2009. The subject development will be located outside of the buffer zone and is proposed to maintain undisturbed any existing vegetation growing on and below the top of bank. Refer to slope stability report updated on September 2020 enclosed in Appendix D.

## **1.3 Proposed Development Plan**

The subject site is currently vacant. As illustrated on the Conceptual Site Plan, Figure SP1, enclosed in Appendix A, the new residential development would consist of fifty-

three (53) townhouse units, twenty (20) back-to-back townhouses units and one (1) triplex/Rental unit, with a total of 74 residential units. The subject site is currently accessed from Eagle Street and all the residential units will be fronting a private condominium roadway network connecting to municipal road Eagle Street by two point of vehicular access. A 7.50m wide and a 8.20m wide vehicular accesses are proposed at the west and east limit of the site off Eagle Street.

Pedestrian walkways will be provided internally and well-connected to the existing public sidewalk network. A 3.0m right of way widening block is also proposed along Eagle Street Frontage.

The townhouses units will be owned under one single condominium corporation, therefore only one set of sanitary, storm and water service connection to municipal systems will be required for the entire future development.

## 2 Site Grading

The existing drainage pattern indicates that the subject site naturally drains in a north easterly directly towards Western Creek.

The northern portion of the site, of approximately 3.06 ha which represents almost 60% of the entire site, has been identified as an Open Space area and will remain undisturbed. The balance of the site, identified as developable area of 2.03 ha, will be graded to ensure that the storm drainage is self-contained. Driveways, road and laneway drainage will be directed towards a local low point at the internal road where both Low Impact Development (LID) measures and underground facilities will be located to capture and treat the storm drainage prior to discharge towards the Western Creek Ravine as per pre-development conditions. It is proposed to match the existing grade at the southern limit of the 6.0m buffer block to ensure that existing grading is maintained within the Open Space area.

Refer to preliminary grading plan, **Figure 3** enclosed in **Appendix B**.



### **3 WATER SERVICING**

#### **3.1 Existing Water Servicing**

The surrounding development provides for a strong and well-looped water distribution network, with a connection to the boundary main on Yonge Street. An existing 300 mm diameter municipal main running along Eagle Street is available to service the subject site. Refer to **Figure 4** enclosed on **Appendix B**.

#### **3.2 Proposed Water Servicing**

The proposed development will be serviced by the existing 300mm diameter municipal main running along Eagle Street. Refer to **Figure 4** enclosed in **Appendix B** for proposed watermain connection details.

The subject site is proposed to be serviced by a 150mm and 200 mm diameter watermains that will be connected into the existing municipal watermain running on Eagle Street. Domestic service to the residential units will be via service connection laterals much like standard municipal water connections. Fire protection will be provided with on-street hydrants, also in accordance with typical municipal criteria.

It is recommended that on-site hydrant flow- and pressure-tests be carried out prior to detailed design to ascertain the available operating range of the existing municipal water system.

#### **3.3 Proposed Water Demands**

The water demand was calculated using a population equivalent of 2.88ppu for the residential units and 1.95 ppu for apartment units. The average water demand was calculated based on a on rate of 300 L/cap/d and the Town recommended peaking factors of 2.0 for maximum day and 3.0 for peak hour demand. The required maximum day domestic flow for the development is 1.5 L/s and a peak hour demand of 2.25 L/s. Refer to table 3.3 and triplex below.

**Table 3.3**

Site Description	Total Population (people)	Ave Day Demand (300 L/c/d)	Max Day Demand (2.0 Factor)	Max Hour Demand (3.0 Factor)
Residential Units	210	0.73 L/s	1.46 L/s	2.2 L/s
Triplex Unit (3 apartments)	6	0.0210	0.042L/s	0.063 L/s
Total flows			1.5 L/s	2.263 L/s

Preliminary watermain sizing was simulated using EPANet V2. A minimally available average-day pressures at Eagle Street (50 psi, 400 kPa) was assumed for the model.

Three water demand scenarios, peak daily demand plus fire flow, peak hourly demand, and minimum hourly demand, have been simulated using EPANET 2 modeling software to ensure the desired pressures and flows for the subject site are delivered under various demand scenarios.

Refer to table 3.3.1 enclosed in Appendix C for the Nodal demand calculations.

The following minimum values are used to calculate the water demands for this site in accordance with the City standards:

The summary of analysis result is provided in the following Table 3.3.2

**Table 3.3.2**

No	Scenarios	EPANET Results	City Criteria
1	Max. pressure during minimum hourly demand (kpa)	400.70	< 550 (Ok)
2	Min. pressure during the peak hourly demand (kpa)	400.79	> 350
3	Min. pressure during max. peak daily demand + fire	287.07	> 140

The above summary of EPANET 2 modeling result shows that proposed watermain system meets the Town’s standard criteria for required pressures for noted scenarios.

Refer to EPANET result output enclosed in appendix C.

Prior to detail design, a flow test on the existing hydrants will be performed to confirm available pressure and supply and to confirm the sizing of the internal watermain system.

**The proposed 150 mm and 200mm diameter watermain will be tapped off the existing 300mm diameter watermain running on Eagle Street to provide fire and domestic service.**

## 4 SANITARY SERVICING

Research of the Town archives was unable to locate design sheets or other hydraulic calculations for the existing Eagle Street sewer systems. However, it is confirmed that an existing 250mm diameter sanitary sewer is draining easterly to service the surrounding area based on a sketch (Operation Storm Network 2009) provided by the Town of Newmarket. The sketch is enclosed on Appendix B in this report. Based on field observation an existing Sanitary manhole at the south east corner is identified. Based on correspondence between the landowners, Delcan consultants and the Town of Newmarket, it is confirmed that the downstream sanitary sewers (western sanitary subtrunk) were designed to accommodate the future residential development within the subject lands. Refer to historical documentation pertaining to western sanitary subtrunk, sewer dated 1984 on Appendix D.

### 4.1 Proposed Sanitary Servicing

It is proposed to connect into the existing sanitary sewer system on Eagle Street, providing a 200mm diameter PVC sanitary service connection and a control manhole at the property lane. The existing sanitary control manholes has and outlet invert at approximately elevation 255.99m.

For proposed sanitary connections details refer to **figure 5**, enclosed in **Appendix B**.

### 4.2 Sanitary Sewage Flows Estimates

The proposed development comprises 73 Townhouse units, and 1 triplex having an equivalent population of 216 persons as outlined in the following table 4.2.

**Table 4.2** *Population estimated*

Sewage Generation Components and Criteria	Total # of Units	PPU	Total Population
Townhouses	73	2.88	210
Triplex (3 apartments)	3	1.95	6
<b>Total Proposed Population (Residential)</b>			<b>216</b>

The sanitary sewage flow estimates are calculated based on the Engineering Design Standards and Criteria of City of Newmarket, the. Using the above population estimates, the future sanitary sewerage rate from the subject site is calculated as follow.

Proposed Site Design Flow:

*Peak Flow Design Parameters*

Residential I Area = 2.03 ha  
Total Population = 216 p  
Average daily per capital flow (as per town std) = 360 L/cap/day

**Peaking Factor** =  $1 + \{14 / (4 + (P/1000)^{0.50})\} =$

Where: M = ratio of peak flow to average flow  
P = Total equivalent population

**Peaking Factor** = 4.14

**Infiltration**

Infiltration rate = 0.30L/s/ha as per MESP dated in March 2017  
= 0.609L/s

**Calculation of Peak Design Flows**

Design flow,  $Q_{\text{SANITARY}} = \text{population} * \text{average daily flow} * \text{Peaking factor} + \text{Infiltration flow}$   
 $= 360 \text{ L/c/day} \times 216 \times 4.00 / 86,400 / 1000 \text{ m}^3/\text{s} + 0.00069 \text{ m}^3/\text{s}$   
 $= \underline{\underline{0.00429 \text{ m}^3/\text{s}}} = \underline{\underline{4.29\text{L/s}}}$

**A 200mm pipe at minimum 0.50% has enough capacity to accommodate the design flow of 4.29L/s generated by the subject site.**

## **5 STORM DRAINAGE AND STORMWATER MANAGEMENT**

The stormwater management plan for the subject site will be designed in accordance with the Town of Newmarket Stormwater Criteria in conjunction with the Best Management Practice guidelines in the MOE SWMPs Manual and Low impact Development Guidelines by LRSCA Technical Guidelines and other Standards mentioned in the Engineering Design Standards and Criteria of Town of Newmarket. This site will comply with Lake Simcoe Protection Plan (LSPP) polices 4.8 to 4.12. During detailed design stage these polices will be implemented on the subject site.

The following sections will detail the pre- and post-development conditions and describe how the targets can be achieved on site.

Minor storm sewers within the subject lands will be capture the 100-year design storm flow generated from the residential/road areas as per the current storm drainage design criteria of the Town of Newmarket and will be collected by catchbasins connected to the storm sewer which discharges into an underground tank, to ultimately discharge into the existing creek as per pre-development drainage pattern.

The storm drainage system for the subject site will be designed to control the storm runoff to predevelopment levels prior to discharging into the existing creek.

Any resulting post-development runoff in excess of the original design discharge rate must be controlled or detained on-site.

All storm sewer flows in excess of the 100-year storm is proposed to remain overland, conveyed to private roads and finally into the Creek for emergency exit. Approximately 85% of the subject development will be tributary to the private road overland flow route. The remaining lands (rear yards, landscape areas) will drain northerly towards Western Creek as pre-development conditions.

### **5.1 Existing Storm Servicing**

Through a review of Town archives and drawings of the surrounding road network, it is known that a 300 mm diameter storm sewer is available along Eagle Street.

Research of the Town archives was unable to locate design sheets or other hydraulic calculations for the existing Eagle Street sewer systems. However, it is confirmed that a 300mm diameter storm sewer is draining easterly to service the surrounding area based

on sketch (Operation Storm Network 2009) provided by the Town of Newmarket. The sketch is enclosed on Appendix B of this report.

Based on the existing topographical survey, to determine the residual capacity of the existing storm sewer system on Eagle Street, a drainage plan and a design sheet was prepared by this office. An overall runoff coefficient of 0.45 was assumed for the existing residential development draining to this system; as the actual storm sewer slopes are not shown on the drawings provided by the Town, it was assumed that the existing pipe slope is similar to the sanitary sewer slope.

Refer to storm drainage plan **Figure 2** enclosed on **Appendix B** and the storm design sheet Table B1 enclosed on Appendix C.

## 5.2 Proposed Post-development conditions.

### 5.2.1 Water Balance

The primary objective of the Lake Simcoe Protection Plan (LSPP) is to encourage a treatment train approach to water balance, such that the natural hydrologic cycle is maintained and managed through control of urbanized runoff.

To determine the pre- and post- development water budget an assessment completed by Soil Engineers Ltd, on July 15,2020 identified the subject site development with an infiltration deficit of 1637.79m<sup>3</sup>/year.

Assuming conservatively that there is a minimum of 10 rain events per year, the LIDs off-site should be designed to retain and infiltrate a minimum of **163.78m<sup>3</sup>** per event (10 event per year contributing to 1637.79m<sup>3</sup>/year

It is recommended that this target to be achieved through the application of infiltration measures where soil conditions permit.

Stormwater Best Management Practices (BMPs) are measures to manage the quality and quantity of urban runoff to mitigate drainage impacts. A treatment train approach to BMPs can be divided into three groups as follows:

- **Source** controls such as roof leaders discharging to grass or soakaway pits;
- **Conveyance** controls such as grassed swales or vegetative filter strips; and,
- **End-of-pipe** controls such as communal extended detention ponds.

In reviewing options, each alternative BMP was evaluated based on its capabilities, limitations, physical constraints associated with implementation on the specific site, and its effectiveness in achieving the stormwater management objectives. BMPs should ideally accomplish the following goals:

- Emulate as closely as possible the hydrological conditions of the site in its existing condition.
- Reduce nutrient and pollutant loadings in untreated urban runoff.
- Minimize temperature increases in treated runoff.
- Integrate with the planned urban form and municipal service requirements; and,
- Be reasonably cost effective in comparison to other options and have acceptable future maintenance requirements for the local municipality.

The first step in the selection process is to review BMPs based on the following screening factors that focus on:

- Suitability of study area soils and groundwater elevations (where known);
- Existing hydrogeological relationship of site drainage to adjacent tributaries.
- Size of contributing drainage areas.
- Compatibility with urban form.
- Municipal servicing requirements; and,
- Water quality control effectiveness.

It is also important to promote infiltration where soils are suitable to help offset as much as possible the reduction in infiltration due to increased impervious area from the proposed development. Therefore, infiltration practices should be reviewed at the detail design stage to determine viable lot level and conveyance controls such as the following:

- Roof leaders directed to rear yard ponding areas, soakaway pits, cisterns, rain barrels, etc.
- Infiltration trenches.
- Bioretention swales.
- Vegetated filter strips; and
- Stream and valley corridor buffer strips.

Based on the proposed layout, Bioretention swales, grassed swales and pavement pavers are feasible BMP devices.



- **Bioretention Swale**

Bioretention systems are stormwater best management practices (BMPs) that use media filtration to treat stormwater runoff. These systems use vegetation, such shrubs, and grasses, and sand or aggregate media to remove pollutants from stormwater runoff.

A bioretention system is suitable for this site as it provides not only vegetated filtration and nutrient intake, but routing stormwater through vegetation also helps reduce water temperature. Furthermore, the bioretention swale serves a dual function as they will improve infiltration into the subsurface, enhancing recharge and moisture capture by the vegetation.

The Bioretention swale provide a volume of 29.8m<sup>3</sup> as follow:

$$\text{Volume provided} = 124.30\text{m}^2 \times 0.6\text{m (H)} * 0.4 = \mathbf{29.8\text{m}^3}$$

The geotechnical report prepared by Soil Engineers LTD dated in October 2004, 2009,2011 and updated by letter prepared by Soil engineers Ltd dated in September 2020 identifies the soil present on the subject site as silty clay and sandy silt till.

The estimated hydraulic conductivities range from  $2.8 \times 10^{-6}$  m/sec to  $8.4 \times 10^{-5}$  m/s confirming the low to moderate permeability for the native subsoil present on the subject site, therefore the installation of a subdrain above the permanent water level of the LID is recommended.

- **Enhanced Grass swale**

Enhanced grass swale is vegetated open channels deigned to convey and attenuate stormwater runoff and incorporate design features such a modified geometry and check dams that improve the contaminant removal and runoff reduction functions of simple gras channel and roadside ditch designs.

The Enhanced grass swale provide a volume of 44.7m<sup>3</sup> as follow:

$$\text{Volume provided} = 207 \text{ m (L)} \times 0.9\text{m (W)} \times 0.6\text{m (H)} * 0.4 = \mathbf{44.7\text{m}^3}$$

Installation of a subdrain along the grass swale, above the PWL is recommended as the estimated hydraulic conductivity of the native sol is less than 15mm/hr

- **Pervious pavement (Turfstone pavement):** Turfstone pavement will be implemented on a portion of the proposed laneway to allow percolation or infiltration of stormwater through the surface into the soil below where the water is

naturally filtered, and pollutants are removed. The proposed permeable pavement is located north of the proposed amenity area and south of Block #7, refer to Figure 2 enclosed on Appendix B.

Void ratio = 0.4

Depth = 0.6m

Area = 382 m<sup>2</sup>

Volume = 0.40 x 0.6m x 382m<sup>2</sup> = **91.68 m<sup>3</sup>**

The total volume provided for water balance purposes is **166.18m<sup>3</sup>** = (29.8m<sup>3</sup>+44.7m<sup>3</sup>+91.68m<sup>3</sup>).

### 5.2.2 Allowable Peak Flow- Pre-Development

In accordance with the LSRCA guidelines for Stormwater Management Section 2.2.1 the peak flows rate for major development and linear development are not exceed the correspond pre-development peak flow rates 1 in 2 year, 1 in 5 year, 1 in 10 yr, 1 in 25 year, 1 in 50 year and 1 in 100 year storm events. post-development peak flow rates.

It is proposed to control the peak flows for each storm event (2 years, 5 years, 25 years 50 year and 100 years) to match the LSRCA peak flow targets.

The post-development storm flows have been quantified using the Modified Rational Method, as follow:

The allowable release rate for each storm event was calculated using the Town of Newmarket Rainfall Intensity equations as follows:

**2-year storm rainfall intensity:**

$$I_2 = 648 * (T+4)^{-0.784}$$

**5-year storm rainfall intensity:**

$$I_5 = 930 * (T+4.0)^{-0.798}$$

**25-year storm rainfall intensity:**

$$I_{25} = 1100 * (T+2)^{-0.776}$$

**50-year storm rainfall intensity:**

$$I_{50} = 1488 * (T+3)^{-0.803}$$

**100-year storm rainfall intensity:**

$$I_{100} = 1770 * (T+4)^{-0.82}$$

Where:

$i$  = rainfall intensity (mm/hr)

$t_c$  = time of concentration (min) = 10

$I_2 = 81.84\text{mm/hr}$        $I_5 = 113.20\text{mm/hr}$        $I_{25} = 159.937\text{mm/hr}$        $I_{50} = 189.717\text{mm/hr}$

$I_{100} = 203.305\text{mm/hr}$

A pre-development runoff coefficient of **R=0.25** is to be used for computing the target peak flows;

$Q_{2\text{ yr Post}}$  at Runoff coefficient of 0.75 to be e controlled to  $Q_{2\text{ yr Pre}}$  at Runoff coefficient of 0.25  
 $Q_{5\text{ yr Post}}$  at Runoff coefficient of 0.75 to be e controlled to  $Q_{5\text{ yr Pre}}$  at Runoff coefficient of 0.25  
 $Q_{25\text{ yr Post}}$  at Runoff coefficient of 0.75 to be e controlled to  $Q_{25\text{ yr Pre}}$  at Runoff coefficient of 0.25  
 $Q_{50\text{ yr Post}}$  at Runoff coefficient of 0.75 to be e controlled to  $Q_{25\text{ yr Pre}}$  at Runoff coefficient of 0.25  
 $Q_{100\text{ yr Post}}$  at Runoff coefficient of 0.75 to be e controlled to  $Q_{100\text{ yr Pre}}$  at Runoff coefficient of 0.25

The allowable release rate for each storm event is calculated as follows:

$$Q_{allow} = \frac{A_t i R}{360} (m^3 / s)$$

Where:

$Q_{allow}$  = Peak Stormwater Flow ( $m^3/s$ )

$R$  = Runoff coefficient = 0.450

$i$  = Rainfall intensity (mm/hr) =

$A_t$  = Total developable site Area (ha) = 2.03 ha

$$Q_{2\text{yr-allow}} = \frac{2.03 * 0.25 * 81.84}{360} = 0.115 \text{ m}^3/\text{s}$$

$$Q_{5\text{yr-allow}} = \frac{2.03 * 0.25 * 113.20}{360} = 0.159 \text{ m}^3/\text{s}$$

$$Q_{25\text{yr-allow}} = \frac{2.03 * 0.25 * 159.937}{360} = 0.225 \text{ m}^3/\text{s}$$

$$Q_{50\text{yr-allow}} = \frac{2.03 * 0.25 * 189.717}{360} = 0.267 \text{ m}^3/\text{s}$$

$$Q_{100\text{yr-allow}} = \frac{2.03 * 0.25 * 203.305}{360} = 0.287 \text{ m}^3/\text{s}$$

Flows from certain areas within the site due grading cannot be controlled (Areas U1, U2, U3 and U4, refer to figure 6 enclosed in Appendix B). Therefore, drainage from these areas will be considered uncontrolled flow to municipal system and flow will be deducted from maximum allowable release rate.

Uncontrolled flow is calculated as follows:

$$Q_{2\text{yr}} = \frac{0.287 * 0.25 * 81.84}{360} = 0.016 \text{m}^3/\text{s}$$

$$Q_{5\text{yr}} = \frac{0.287 * 0.25 * 113.20}{360} = 0.022 \text{m}^3/\text{s}$$

$$Q_{25\text{yr}} = \frac{0.287 * 0.25 * 159.937}{360} = 0.032 \text{m}^3/\text{s}$$

$$Q_{50\text{yr}} = \frac{0.287 * 0.25 * 189.717}{360} = 0.038 \text{m}^3/\text{s}$$

$$Q_{100\text{yr}} = \frac{0.19 * 0.25 * 203.305}{360} = 0.041 \text{m}^3/\text{s}$$

Therefore, the net allowable release rate is calculated as follows:

$$Q_{\text{allow } 2\text{yr}} = 0.115 \text{ m}^3/\text{s} - 0.016 \text{m}^3/\text{s} = 0.099 \text{m}^3/\text{s}$$

$$Q_{\text{allow } 5\text{yr}} = 0.159 \text{m}^3/\text{s} - 0.022 \text{m}^3/\text{s} = 0.137 \text{m}^3/\text{s}$$

$$Q_{\text{allow } 25\text{yr}} = 0.225 \text{ m}^3/\text{s} - 0.032 \text{m}^3/\text{s} = 0.193 \text{m}^3/\text{s}$$

$$Q_{\text{allow } 50\text{yr}} = 0.267 \text{ m}^3/\text{s} - 0.038 \text{m}^3/\text{s} = 0.229 \text{m}^3/\text{s}$$

$$Q_{\text{allow } 100\text{yr}} = 0.287 \text{ m}^3/\text{s} - 0.041 \text{m}^3/\text{s} = 0.246 \text{m}^3/\text{s}$$

### 5.2.3 Post-development Discharge

To meet the stormwater quantity objectives, the subject site is proposed to provide on-site water quantity control up to the maximum allowable release rate for each storm event. The required storage volume has been calculated using Modified Rational Method included as Tables 5.2.3, 5.2.4 5.2.5 ,5.2.6 and 5.2.7 on Appendix C and a Runoff Coefficient of R=0.70 as outlined in the following table 5.2.2.1

**Table 5.2.2.1 Post-Development Composite Runoff Coefficient**

Surface Area component	Area (ha)	C	Weighted Runoff Coeff. "C"
			Area x C
Roofs	0.784	0.9	0.706
Roads/Sidewalks	0.549	0.9	0.494
Landscape	0.697	0.25	0.174
<b>Totals</b>	<b>2.03</b>		<b>1.374</b>
			1.374/2.03
	R= AxC/TOTAL AREA		0.68

Therefore, a runoff coefficient of 0.68 is used for the onsite storage calculations.

The runoff coefficient was adjusted using the routing coefficients as recommended the MTO, refer to design chart 1.07 (MTO) for each rain event.

From table 5.2.5 enclosed on Appendix C, the maximum required onsite storage for the subject site is 462.09 m<sup>3</sup> which will be provided by utilizing a below-grade storage tank.

- A storm trap, or approval equal, is sized as follows:

$$\begin{aligned} \text{Required volume} &= 462.09 \text{ m}^3 \\ \text{Tank A Volume} &= A \times C_f \times h \\ &= 240\text{m}^2 \times 1.30 \text{ (h)} \times 0.90 \\ \text{Volume (Tank A)} &= 280.8 \text{ m}^3 \end{aligned}$$

- Storage pipes  
Volume = 24.23m<sup>3</sup>
- LID  
Volume = 166m<sup>3</sup>

In summary, the net available storage is 471.03m<sup>3</sup> when utilizing a combination of 26m length of 675mm storm pipe, 21 m length of 750mm stm pipe, 44m length of 450mm stm pipe, an underground tank, a bioretention, a grassed swale and permeable paver.

The internal piping has been designed to convey the 100-year flow generated by the site

to the tank (A).

The houses should not be connected into the storm sewers to avoid backing up into the basement.

To control the storm flow to the allowable release rates during each storm event, 2yr, 5yr, 25yr, 50 yr and 100-year control structures are required and will be sized at the detailed design stage. The control structures will be installed upstream of the stormfilter/OGS.

For location of the underground Tank (A) refer to figure 5, enclosed in Appendix B.

#### **5.2.4 Stormwater Quality Control**

The town **requires** the minimum acceptable level of quality control is to provide an *Enhanced or Level 1* protection in accordance with MOE guidelines, and consistent with the LSRCA Lake Simcoe Protection Plan Policy (LSPP) DP-4.8.

Additionally, this site falls within the Lake Simcoe drainage shed, and as part of the LSPP, all developments will be required to demonstrate and implement a reduction in Total Phosphorus (TP) runoff from the site, as a means to reduce loading to and eutrophication of Lake Simcoe.

The water quality control targets for the subject site are presented in the following subsections.

As per LSPP 4.10-DP and 4.11-DP, the condo corporation will be responsible to inspect, monitor and maintain the system.

##### **5.2.4.1 TSS removal**

The subject site will require best-practice treatment of stormwater runoff to achieve 80% TSS removal. Storm runoff from the site consists of the landscape, roof and pavement areas. Runoff from the roof areas is considered clean, while the landscape area runoff will attain an 80% TSS removal by natural filtration.

The overall baseline TSS removal efficiency is presented in the following Table 5.2.4.1

**Table 5.2.4.1 Baseline TSS Removal Rate and Average Runoff Coefficient**

Surface Area Component	Area	Percent Area	Baseline TSS Removal Rate	Weighted TSS Removal Rate
	(m <sup>2</sup> )	(%)	(%)	
Roofs	0.784	38.54	80%	30.83%
Roads/Sidewalks	0.549	27.00	0%	0.0%
Landscape	0.701	34.46	80%	27.57%
<b>Totals</b>	<b>2.034</b>	<b>100%</b>		<b>58.40%</b>

The baseline weighted average TSS removal is 58.40%, which does not meet the targeted 80% long-term average rate required by the Town of Newmarket.

Therefore, the entire post-development drainage areas are routed into an Oil-Grit Separator (OGS). Newer media-filter based technology such as the Contech Stormfilter are recognized to provide a much higher removal rate of TSS (80%) a TP (79%) The Stormfilter would also function as pre-treatment settling chamber, removing larger solids, bitumous runoff, and the initial TSS settling. Based on the sizing report prepared by the manufacture, the specific model is a Contech Stormfilter SFPD 0822” PhospoSorb .

A Stormfilter & TP model has been selected to treat the subject site. Refer to detailed Stormfilter sizing report enclosed in Appendix C.

**5.2.4.2 TOTAL PHOSPHOROUS**

A primary cause of eutrophication of Lake Simcoe is the increase in nutrient loading due in part to the urban effects of increased runoff volume and lawn and landscape maintenance practices. Lake Simcoe Protection Plan (LSPP) Policy 4.8e requires that:

*“An application for major development shall be accompanied by a stormwater management plan that demonstrates...  
 e. through an evaluation of anticipated changes in phosphorus loadings between pre-development and post-development, how the loadings shall be minimized.”*

For the subject site, best efforts to promote LID measures for other stormwater quality control targets (TSS) and hydrologic water balance include:

- On-site storage for the first 5mm for water balance
- End-of-pipe quality control (OGS device)

The estimation of nutrient runoff within the LSPP watershed has been simplified with the Phosphorus Budget Guidance Tool for New Development in the Lake Simcoe Watershed (the Tool), which is a relational database of pre-calculated nutrient loading and mitigation factors calibrated specifically for the Lake Simcoe watershed.

#### **5.6.1 BMP Performance – TP Reduction**

The Tool was run for the subject site, using the East Holland subwatershed data, and following the guidance in describing pre-and post-development land use from Table 1 in the Tool Guidebook.

The post-development drainage from subject site are modeled to be directed to the OGS as having media (*PhosphoSorb*) to removes total phosphorus (TP) from the stormwater runoff by absorbing dissolved-P and filtering particulate-P simultaneously. Field tests of the *PhosphoSorb* media showed a load reduction 79% total phosphorus.

With the addition of the proposed LID measures, the additional TP loading is reduced to 0.05 kg/yr.

The TP model output is attached in Appendix C.



## 6 EROSION AND SEDIMENT CONTROL

Erosion and sediment control should be implemented for all construction activities within the subject site, including topsoil stripping, parking lot construction, foundation excavation and stockpiling of materials. The basic principles considered to minimize erosion and sedimentation and resultant negative environmental impacts include:

- Minimize local disturbance activities (e.g. limit area-wide grading);
- Expose the smallest possible land area to erosion for the shortest possible time;
- Implement erosion and sediment control measures before the outset of construction activities; and,
- Carry out regular inspections of erosion and sediment control measures and repair or maintain as necessary.

The proposed grading, servicing and building construction should be carried out in such a manner that a minimum amount of erosion occurs and such that sedimentation facilities control any erosion that does occur. Erosion and sediment control measures should include but not be limited to the following:

- Erection of silt fences around all site perimeters and double silt fence along the buffer of the top bank
- Provide sediment traps (e.g. rock check dams, straw bales, scour basins) along interceptor swales and points of swale discharge.
- Inlet controls at catchbasins, comprising filter cloth overlain with rip-rap;
- Implement a weekly street sweeping and cleaning program for any mudtracking onto Eagle Street;
- Provide gravel “mud mats” at construction vehicle access points to minimize off-site tracking of sediments; and,
- Confine refueling/servicing equipment to areas well away from inlets to the minor system or major system elements.
- All waste and unused building materials (including garbage, cleaning wastes, wastewater, toxic materials, or hazardous materials) shall be properly disposed of and not allowed to be mixed with and carried off by runoff from the site into a receiving watercourse or storm sewer.

Removal of the erosion and sediment controls should be done once construction is completed and sediment run-off from the construction activities has stabilized.

## 7 CONCLUSIONS AND SUMMARY RECOMMENDATIONS

This functional servicing and stormwater management report demonstrates that the proposed residential development within the subject site can be accommodated by the existing local infrastructure. Specifically:

- **Water Service** will be provided by existing 300 mm diameter PVC service connection located along on Eagle Street. A 150 mm and 200mm lateral connection will be tapped off the main to provide residential water demand.
- **Sanitary Service** is accommodated by the existing 250 mm diameter sanitary sewer running on Eagle Street. A 200mm diameter service lateral is proposed to service the subject development.
- **Quantity Controls** will be provided for each storm event using a storage tank., storage pipes and LID measures. Control structures located upstream of the OGS, will control the release flow for each rain event.
- **Quality control** (Enhanced Level) will be provided by an OGS located downstream for the storage tank.

**TP reduction** during post-development is achieved with a Stromfilter type filter.

- **Water balance** will be provided for Enhanced grass swale, pavement pavers and bioretention swale.
- **Erosion and Sediment Controls** will need to be implemented during development until the site has been stabilized with groundcover. Erosion and sediment control drawing show existing trees, silt fence, mud mat, and trees to be removed before earthworks. Silt fence to be inspected by arborist prior to works.

We trust that this analysis is complete and satisfactory. Should you require additional information, please contact the undersigned.

Respectfully Submitted,  
**MASONGSONG ASSOCIATES ENGINEERING LIMITED**



Lucila Ensuncho, M.A.Sc., P.Eng.  
Principal

H:\PROJECTS\99\598\2020\Reports\FSR\99-598-fsr-rev2.doc

A handwritten signature in blue ink, appearing to read "Isabel Strauch".

Isabel Strauch,  
Municipal Designer

## **Appendices**

## **Appendix A**

### Site Plan and Survey

**SURVEY INFORMATION:**

SURVEY INFORMATION IS TAKEN FROM A COMPILED PLAN OF SURVEY ENTITLED: PART OF LOTS 2 AND 3 REGISTERED PLAN 49 TOWN OF NEWMARKET REGIONAL MUNICIPALITY OF YORK PREPARED BY: YOUNG & YOUNG SURVEYING INC., OLS 2 HOLLAND DRIVE, UNIT 5 BOLTON, ON L7E 1E1 DATED: MARCH 1, 2011

**PROPERTY INFORMATION:**

PROPERTY AREA: VALLEY LANDS 28 477 SM (7.04 AC) BUFFER ZONE 2 114 SM (0.52 AC) NET DEVELOPMENT AREA 19 742 SM (4.88 AC) PROPOSED ROAD WIDENING 589 SM (0.15 AC) TOTAL PROPERTY AREA 50 922 SM (12.58 AC)

PROPOSED AREAS: PRIVATE ROADS AND PARKING 4 869 SM SIDEWALKS 621 SM REMAINING LOT AREA 14 252 SM (3.52 AC)

**PROPOSED BUILDING INFORMATION:**

TYPE	DESCRIPTION	UNITS	UNIT FOOTPRINT (SQ.M.)	UNIT GFA (SQ.M.)	TOTAL GFA (SQ.M.)
T1	3 STOREY TOWNHOME	11	80.3	196.7	2,163.7
T2	3 STOREY TOWNHOME	7	78.8	220.8	1,545.6
T3	3 STOREY TOWNHOME	5	57.5	169.5	847.5
T4	2 STOREY TOWNHOME	4	92.8	176.8	707.2
T5	3 STOREY TOWNHOME	13	85.3	240.3	3,123.9
T6	3 STOREY TOWNHOME	6	105.8	301.4	1,808.4
T7	3 STOREY TOWNHOME	6	106.0	274.0	1,644.0
T8	3 STOREY TOWNHOME	1	54.2	162.6	162.6
T9	3 STRY. B.T.B. T.H.	20	58.6	168.4	3,368.0
		73			15,370.9
T10	TRIPLEX	3	185.5	185.5	556.5
		76			15,927.4

**SITE BUILDING STATISTICS:**  
 LOT COVERAGE 41% (5,885 SQ.M. / 14,252 SQ.M.)  
 FSI 0.81 (15,927 SQ.M. / 19,727 SQ.M.)  
 UNITS PER HA 38.6 (76 U / 1.97 HA)

**PROPOSED PARKING INFORMATION:**


PARKING PER NEWMARKET ZONING BY-LAW 2010-40

UNIT TYPE	# UNITS	PARKING RATES	REQUIRED	PROVIDED	DIFFERENCE
TOWNHOUSE/ STACKED/ TRIPLEX	76	1.5	114	91	-23
VISITOR	76	0.25	19	35	16
			133	126	-7

PARKING PER NEWMARKET ZONING BY-LAW 2019-06

UNIT TYPE	# UNITS	PARKING RATES	REQUIRED	PROVIDED	DIFFERENCE
TOWNHOUSE/ STACKED/ TRIPLEX	76	1.0	76	91	15
VISITOR	76	0.15	11	35	24
			85	126	39


**MAP KEY:**



SCALE: 1:4000


**LEGEND:**

- EXISTING CONTOUR
- - - EX. 15M BUFFER ZONE FROM CREEK
- - - EX. REGIONAL FLOODLINE
- EXISTING TREE TO BE PRESERVED
- - - EXISTING EASEMENT
- - - LIMIT OF DEVELOPMENT AREA
- - - LIMIT OF PROPERTY
- - - STAKED TOP OF BANK



CONCEPTUAL DRAWING TO BE READ IN CONJUNCTION WITH SUPPORTING BACKGROUND STUDIES SUBMITTED UNDER OFFICIAL PLAN AMENDMENT APPLICATION (09-NP-11-09) AND ZONING BY-LAW AMENDMENT APPLICATION (D14-NP-11-09)

**NORTH:**



No.	DESCRIPTION	BY	DATE
2	ADDED NOTES		FEB 2/21
1	REVISED CONCEPTUAL DRAWING FOR OPA / ZONING PROPOSAL		JULY 2020

**OWNER:**

**MILLFORD**  
 DEVELOPMENT LIMITED  
 P.O. Box 215  
 Newmarket, ON L3Y 4X1  
 Tel: (905) 778-1818  
 Fax: (905) 778-0877


55 EAGLE STREET  
 CONDOMINIUM RESIDENTIAL TOWNHOMES  
 AND TRIPLEX PROPOSAL  
 TOWN OF NEWMARKET  
 REGIONAL MUNICIPALITY OF YORK

**CONCEPTUAL SITE PLAN**

DESIGNED BY: CAD	Drawing No. <b>SP1</b>
CHECKED BY:	
DATE: JULY 2020	
SCALE: 1:500	



REGISTERED PLAN 527



NOTE

NO UNDERGROUND SERVICES HAVE BEEN LOCATED OR ILLUSTRATED  
 THIS PLAN IS DERIVED FROM COMPILED DATA AND NOT FIELD MEASUREMENTS AND SHALL NOT BE USED FOR TRANSACTION OR MORTGAGE PURPOSES.

BENCHMARK

YORK REGION BENCHMARK No. 55-700  
 ELEVATION = 268.79 Meters

DWG TP1

LEGEND

- |     |         |                  |
|-----|---------|------------------|
| TL  | DENOTES | TRAFFIC LIGHT    |
| MH  | DENOTES | MAINTENANCE HOLE |
| CB  | DENOTES | CATCH BASIN      |
| LS  | DENOTES | LIGHT STANDARD   |
| HP  | DENOTES | HYDRO POLE       |
| FH  | DENOTES | FIRE HYDRANT     |
| GV  | DENOTES | GAS VALVE        |
| WV  | DENOTES | WATER VALVE      |
| EV  | DENOTES | EXHAUST VENT     |
| GWP | DENOTES | GUY WIRE POLE    |
| GW  | DENOTES | GUY WIRE         |

**YOUNG AND YOUNG SURVEYING INC.**  
 PROFESSIONAL LAND SURVEYORS

BOLTON 2 HOLLAND DRIVE UNIT 5 BOLTON ONTARIO L7E 1E1 PHONE 905-800 FAX 857-4811 DRAWN BY: R.W./G.M.	TORONTO 385 THE WEST MALL SUITE 400 ETOBICOKE, ONTARIO M9C 1E7, 621-2878
--	--

PROJECT 03-B4461

TOP OF BANK ADDED FEB. 25 2003

EAGLE STREET

REGISTERED PLAN 49

TOP OF BANK AS ESTABLISHED BY  
 LAKE SIMCOE CONSERVATION AUTHORITY  
 FEB. 19 2003

BUSH

LOT 94  
 CONCESSION 1  
 EAST OF YONGE STREET

LOT 1

LOT 2

LOT 3

LOT 4

LOT 5

LOT 6

LOT 7

LOT 8

LOT 9

LOT 10

LOT 11

LOT 12

LOT 1

LOT 2

LOT 3

COMPILED PLAN OF  
 PART OF LOTS 2 AND 3  
 REGISTERED PLAN 49  
 TOWN OF NEWMARKET  
 REGIONAL MUNICIPALITY OF YORK

SCALE 1 : 500

0 5 10 20 30 40 50  
 METRES

YOUNG & YOUNG SURVEYING INC.  
 ONTARIO LAND SURVEYORS

©  
 JUNE, 2010

REGISTERED PLAN 527

LOT 94  
 CONCESSION 1  
 EAST OF YONGE STREET

LOT 1

LOT 2

LOT 3

LOT 4

LOT 5

LOT 6

LOT 7

LOT 8

LOT 9

LOT 10

LOT 11

LOT 12

PART 4 65R-27436

PART 3 65R-27436

SUBJECT TO EASEMENT  
 AS INST. No. A51416A

AVENUE ROAD  
 EXTENSION

Top of Bank as staked  
 with LSCA on APRIL 15, 2009

⑧ 27040 m<sup>2</sup>  
 PIN 03598-0309(LT)  
 SUBJECT TO EASEMENT AS IN B430328 AND A51416A

LOT 2  
 PART 1 65R-27436

LOT 3

**NOTE**  
 ALL AREAS ARE APPROXIMATE  
 THIS PLAN IS COMPILED FROM DEPOSITED PLANS 65R-27436 AND  
 65R-30328 AND NOT FIELD MEASUREMENTS AND SHALL NOT BE  
 USED FOR TRANSACTION OR MORTGAGE PURPOSES.





Top of Bank as staked with  
 LSCA on APRIL 15, 2009  
 6 m Buffer Zone

REGISTERED PLAN 49

① 5265 m<sup>2</sup>

⑦ 9303 m<sup>2</sup>

PARCEL	m <sup>2</sup>	ha.	ft <sup>2</sup>	Acres
1	5265	.5265	56,672	1.301
2	489	.0489	5,263	0.121
3	1437	.1437	15,467	0.355
4	534	.0534	5,747	0.132
5	1091	.1091	11,744	0.270
6	5099	.5099	54,886	1.259
7	9303	.9303	100,137	2.299
8	27,040	2.7040	291,058	6.682
9	77	.0077	829	0.019
10	526	.0526	5,662	0.130
11	61	.0061	657	0.015
TOTAL AREA OF PROPERTY		5.0922 ha.	12,583 Acres	



DWG TP2

**YOUNG & YOUNG SURVEYING INC.**  
 PROFESSIONAL LAND SURVEYORS

BOLTON  
 2 HOLLAND DRIVE UNIT 6  
 BOLTON ONTARIO L7R 1E1  
 PHONE 905-8000 FAX 905-8811

EXAMINED BY  
 J.F.G.Y. BSc. O.L.S.



PARTY CHIEF  
 CALC BY B.C.  
 DRAWN BY B.C.

**PROJECT 08-B5861**






## **Appendix B**


Figures 2 to 8 and City drawings



**LEGEND:**

-  Sub-Area No.  
Run Off Coefficient
-  Area (ha)
-  DRAINAGE AREA

 <b>MASONGSONG ASSOCIATES</b>		7800 KENNEDY ROAD SUITE 201 MARKHAM, ONTARIO L3R 2G7 T: (905) 944-0162 www.masong.ca			
MILLFORD DEVELOPMENT LIMITED					
<b>PRELIMINARY STORM SEWER ASSESSMENT ON EAGLE ST.</b>					
DATE: AUG. 2020	SCALE: N.T.S.	DESIGN BY:	DRAWN BY: MAEL/CAD	PROJECT No. <b>99598</b>	FIGURE <b>2</b>





- ▲ Storm Inlet      ● Storm Manhole      ◦ Private Inlet      ◦ Private Manhole      → Gravity Sewer      — Catchbasin Lead      — Private Sewer      ~ Water Course      ■ Green Space      □ Teranet
- ▲ Storm Outfall      ■ Storm Catchbasin      ◦ Private Outfall      ◦ Private Catchbasin      → Culvert      — Rear Yard Catchbasin Lead      — Railway      🌊 Water Body      🌊 LSRCA Floodplain

Sources: Land Parcels - © Teranet Inc. and its suppliers. All rights reserved. May not be reproduced without permission. 2009. Water Network, Operations Gnd - Town of Newmarket/PWES - Operations Centre, 2009. Current as of January, 2009. DISCLAIMER: This mapping is based on the POLARIS parcel fabric product compiled using Land Registry System records and recent surveys and control points where available. This mapping is a representation of the earth's surface and provides estimates of area and distance. It is not a substitute for a legal survey.



Jan. 2009 - SRMap091 - D:\Repository\GIS\Operations\_Summary\_2009.mxd



- LEGEND:**
- STUDY AREA
  - × (175.5) EXISTING ELEVATION
  - × 182.55 PROPOSED ELEVATION
  - ➔ OVERLAND FLOW ROUTE
  - FLOODPLAIN WITH 15m SETBACK
  - FLOODPLAIN
  - EX. TREE TO BE REMAIN

**MASONSONG ASSOCIATES**  
 7800 KENNEDY ROAD  
 SUITE 201  
 MARKHAM, ONTARIO  
 L3R 2C7  
 T: (905) 944-0162  
 www.maeng.ca



---

**MILLFORD DEVELOPMENT LIMITED**

---


**PRELIMINARY GRADING PLAN**



DATE:	SCALE:	DESIGN BY:	DRAWN BY:	PROJECT No.	FIGURE
MAR. 2021	N.T.S.	MAEL/CAD	MAEL/CAD	<b>99598</b>	<b>3</b>



**LEGEND:**


- STUDY AREA
- PROPOSED WATERMAIN LINE
- EXISTING WATERMAIN LINE
- ⊕ PROPOSED HYDRANT
- ✕ PROPOSED VALVE
- EX. TREE TO BE REMAIN

 <b>MASONGSONG ASSOCIATES</b>		7800 KENNEDY ROAD SUITE 201 MARKHAM, ONTARIO L3R 2C7 T: (905) 944-0162 www.maeng.ca			
<b>MILLFORD DEVELOPMENT LIMITED</b>					
<b>WATERMAIN</b>					
DATE:	SCALE:	DESIGN BY:	DRAWN BY:	PROJECT No.	FIGURE
MAR. 2021	N.T.S.		MAEL/CAD	<b>99598</b>	<b>4</b>



**LEGEND:**

- STUDY AREA
- PROPOSED SANITARY LINE
- EXISTING SANITARY LINE
- Area (ha)  
Population
- Flow (L/s)
- BOUNDARY SANITARY DRAINAGE AREA
- EX. TREE TO BE REMAIN



**MASONGSONG ASSOCIATES**



7800 KENNEDY ROAD  
SUITE 201  
MARKHAM, ONTARIO  
L3R 2C7  
T: (905) 944-0162  
www.maeng.ca

---

**MILLFORD DEVELOPMENT LIMITED**

**SANITARY SEWER LAYOUT AND DRAINAGE PLAN**

DATE: MAR. 2021	SCALE: N.T.S.	DESIGN BY:	DRAWN BY: MAEL/CAD	PROJECT No. <b>99598</b>	FIGURE <b>5</b>
--------------------	------------------	------------	-----------------------	-----------------------------	--------------------



**LEGEND:**

- STUDY AREA
- PROPOSED STM LINE
- Area (ha)  
Runoff coefficient
- Area (ha)  
Runoff coefficient
- BOUNDARY STM DRAINAGE AREA
- FLOODPLAIN WITH 15m SETBACK
- FLOODPLAIN
- EX. TREE TO BE REMAIN

**MASONGSONG ASSOCIATES**



7800 KENNEDY ROAD  
SUITE 201  
MARKHAM, ONTARIO  
L3R 2C7  
T: (905) 944-0162  
www.maeng.ca

---





**MILLFORD DEVELOPMENT LIMITED**

**STORM SEWER LAYOUT AND DRAINAGE PLAN**

DATE:	SCALE:	DESIGN BY:	DRAWN BY:	PROJECT No.	FIGURE
MAR. 2021	N.T.S.		MAEL/CAD	<b>99598</b>	<b>6</b>



**LEGEND:**



-  STUDY AREA
-  PROP. ENHANCED SWALE
-  PROP. BIORETENTION SWALE
-  PROP. PAVEMENT PAVERS

**MASONGSONG ASSOCIATES**  
 7800 KENNEDY ROAD  
 SUITE 201  
 MARKHAM, ONTARIO  
 L3R 2C7  
 T: (905) 944-0162  
 www.maeng.ca

**MILLFORD DEVELOPMENT LIMITED**  
**PROPOSED LOW IMPACT DEVELOPMENT (LID)**

DATE: MAR. 2021	SCALE: N.T.S.	DESIGN BY:	DRAWN BY: MAEL/CAD	PROJECT No. 99598	FIGURE 7
--------------------	------------------	------------	-----------------------	----------------------	-------------





**LEGEND:**

- STUDY AREA
- SEDIMENT DOUBLE CONTROL FENCE
- SEDIMENT CONTROL FENCE
- TEMPORARY GRAVEL ACCESS PAD
- TEMPORARY CATCHBASIN SEDIMENT CONTROL DEVICE
- OVERLAND FLOW ROUTE
- EXISTING OVERLAND FLOW ROUTE
- ROCK CHECK DAM
- TEMPORARY INTERCEPTOR SWALE DURING CONSTRUCTION
- DEWATERING DISCHARGE
- EX. TREE TO BE REMOVED
- EX. TREE TO BE REMAIN

**MASONGSONG ASSOCIATES**  
 7800 KENNEDY ROAD  
 SUITE 201  
 MARKHAM, ONTARIO  
 L3R 2C7  
 T: (905) 944-0162  
 www.maeng.ca

**MILLFORD DEVELOPMENT LIMITED**  
**PRELIMINARY SEDIMENT & EROSION CONTROL PLAN**

DATE: MAR. 2021	SCALE: N.T.S.	DESIGN BY:	DRAWN BY: MAEL/CAD	PROJECT No. 99598	FIGURE 8
--------------------	------------------	------------	-----------------------	----------------------	-------------

## **Appendix C**

Design sheet, Waterman Tables, preliminary sizing of OGS

### Table 3.3.1. Nodal Demand Summary

Millford Developments - Eagle Street  
 Town of Newmarket  
 Fire demand = 10,000L/min for estate residential.


Node	Elev	No. Of Units	Density Factor	Demand Units	Demand Pop	Demand Flow (300L/capita/day)	Min Hour	Max Day	Max Hour
			1		2.88 ppu towhouse 1.95 ppu triple.	L/s	0.70	2.00	3.00
100	73.00	1	1	73.00	210.00	0.729	0.510	1.46	2.188
	1.00	1	1	3	5.900	0.020	0.014	0.041	0.061
<b>Total</b>						<b>0.750</b>	<b>0.525</b>	<b>1.499</b>	<b>2.249</b>

Elevation 259.50                      10,000 L/min                      166.667  
 Pressure 58.00 psi                      40.85 m  
 Total Head                      300.35 m

Fire demand and max day (L/s)                      168.17

		Analysis Results	Newmarket Design Criteria	Type of Scenarios
Pressure (Node 100)	29.28 m	287.07 kPA 20.59 psi	140 kPA min 20 psi	Peak Daily Flow Plus Fire Scenario
Pressure (Node 100)	40.87 m	400.70 kPA 28.74 psi	550 kPA max 80 psi	Minimum Hourly Demand Scenario
Pressure (Node 100)	40.88 m	400.79 kPA 28.75 psi	345kPA min 50 psi	Peak Hourly Demand Scenario

# Scheme WaterMain



```

*****
*                               E P A N E T                               *
*                               Hydraulic and Water Quality              *
*                               Analysis for Pipe Networks                *
*                               Version 2.0                              *
*****
    
```

Input File: 99598MAXDAY-FIRE.net

Link - Node Table:

Link ID	Start Node	End Node	Length m	Diameter mm
P-500	1	100	27	150

Node Results:

Node ID	Demand LPS	Head m	Pressure m	Quality
100	168.17	278.74	29.28	0.00
1	-168.17	300.35	0.00	0.00 Reservoir

Link Results:

Link ID	Flow LPS	Velocity m/s	Unit Headloss m/km	Status
P-500	168.17	9.52	800.53	Open

```

*****
*                               E P A N E T                               *
*                               Hydraulic and Water Quality              *
*                               Analysis for Pipe Networks                *
*                               Version 2.0                             *
*****
    
```

Input File: 99598MAXHOUR.net

Link - Node Table:

Link ID	Start Node	End Node	Length m	Diameter mm
P-100	1	100	27	150

Node Results:

Node ID	Demand LPS	Head m	Pressure m	Quality
100	2.25	300.34	40.87	0.00
1	-2.25	300.35	0.00	0.00 Reservoir

Link Results:

Link ID	Flow LPS	VelocityUnit m/s	Headloss m/km	Status
P-100	2.25	0.13	0.27	Open

```

*****
*                               E P A N E T                               *
*                               Hydraulic and Water Quality                *
*                               Analysis for Pipe Networks                  *
*                               Version 2.0                                *
*****
    
```

Input File: 99598MinHOUR.net

Link - Node Table:

Link ID	Start Node	End Node	Length m	Diameter mm
P-100	1	100	27	150

Node Results:

Node ID	Demand LPS	Head m	Pressure m	Quality
100	0.53	300.35	40.88	0.00
1	-0.53	300.35	0.00	0.00 Reservoir

Link Results:

Link ID	Flow LPS	Velocity m/s	Headloss m/km	Status
P-100	0.53	0.03	0.02	Open

**TABLE B1**

TOWN OF NEWMARKET																
ENGINEERING DEPARTMENT																
Design Return Period = 5Yrs, n=0.013																
SHEET NO:		1														
JOB NO:		1999-598														
DATE:		Aug-20														
CONSULTANT		MASONGSONG ASSOCIATES ENGINEERING LTD.														
TOWN FILE NO.:																

LOCATION		RUNOFF					tc (min)	Rainfall Intensity	Cumm Flow	STORM SEWER DESIGN INFORMATION				Full Capacity	Full Velocity	Qact/Qcap	Time (Entry 10 min)	
STREET NAME	MANHOLES		A area (ha)	C runoff coeff.	A x C	ACC. A x C		I (mm/hr)	Q <sub>5</sub> Ax C x Cr x l (L/s)	size (mm)	slope (%)	length (m)	Q full (l/s)	V full (m/s)	SECT. x100%	Sect. (min)	Accum (min)	
	EAGLE STREET	MH100	MH101	0.68	0.45	0.31												
EAGLE STREET	MH100	MH101	0.29	0.45	0.13	0.44	0.51	94.77	114.91	300	4.26	86.0	199.57	2.82	0.58	0.51	10.00	
EAGLE STREET	MH101	MH102	0.35	0.45	0.16	0.59	0.25	92.95	153.37	300	4.26	42.0	199.57	2.82	0.77	0.25	10.51	
EAGLE STREET	MH102	MH103	0.38	0.45	0.17	0.77	0.33	92.09	195.70	300	4.24	56.0	199.10	2.82	0.98	0.33	10.76	
EAGLE STREET	MH103	MH104	0.42	0.45	0.19	0.95	0.32	90.97	241.06	300	4.86	58.0	213.16	3.02	1.13	0.32	11.09	
Subjet Site			2.03	0.63	1.28	1.28			128.00									
EAGLE STREET	MH104	MH105	0.50	0.45	0.23	1.18	0.38	89.90	422.43	450	3.30	74.0	517.88	3.26	0.82	0.38	11.41	

IDF parameters
A= 2464
B= 16
C= 1



Table 5.2.2



On-Site Storage  
Calculator

Project: Residential  
Development  
Project No.: 99-598  
By: IS  
Date: 19-Feb-21

**Town of Nemarket 2-Year**

Location: **Eagle street between Dixon Blvd abd Donlin Ave.**

A = 2.0300 ha  
 Composite C = 0.6800  
 $i_2 = 648 * (T+4)^{-0.784}$   
 $i_2$  (Allowable) = 81.85 mm/hr C=0.25  
 $Q_{Allowable}$  = 0.1154 m<sup>3</sup>/s  
 $Q_{Actual}$  = 0.0990 m<sup>3</sup>/s

$t_c$ (min)	(mm/hr)	$Q_2$ (m <sup>3</sup> /s)	$Q_{stored}$ (m <sup>3</sup> /s)	Peak Volume (m <sup>3</sup> )
1	183.477	0.704	0.605	36.272
2	159.039	0.610	0.511	61.299
3	140.935	0.540	0.441	79.453
4	126.927	0.487	0.388	93.046
5	115.731	0.444	0.345	103.429
6	106.555	0.409	0.310	111.449
7	98.883	0.379	0.280	117.668
8	92.363	0.354	0.255	122.477
9	86.745	0.333	0.234	126.154
10	81.848	0.314	0.215	128.906
11	77.539	0.297	0.198	130.890
12	73.713	0.283	0.184	132.227
13	70.292	0.270	0.171	133.013
14	67.211	0.258	0.159	133.323 ***
15	64.422	0.247	0.148	133.219
16	61.882	0.237	0.138	132.753
17	59.560	0.228	0.129	131.967
18	57.427	0.220	0.121	130.896
19	55.460	0.213	0.114	129.571
20	53.640	0.206	0.107	128.016
21	51.951	0.199	0.100	126.254
22	50.377	0.193	0.094	124.304
23	48.909	0.188	0.089	122.182
24	47.534	0.182	0.083	119.903
25	46.244	0.177	0.078	117.480
26	45.031	0.173	0.074	114.924
27	43.888	0.168	0.069	112.245
28	42.809	0.164	0.065	109.451
29	41.789	0.160	0.061	106.552

Table 5.2.3



On-Site Storage  
Calculator

Project: Residential  
Development  
Project No.: 99-598  
By: IS  
Date: 19-Feb-21

**Town of Nemarket 5-Year**

Location: **Eagle street between Dixon Blvd abd Donlin Ave.**

A = 2.0300 ha  
 Composite C = 0.6800  
 $i_5$  (Allowable) = 113.21 mm/hr  
 $Q_{Allowable}$  = 0.1596 m<sup>3</sup>/s  
 $Q_{Actual}$  = 0.1370 m<sup>3</sup>/s

$i_5 = 930 * (T+4)^{-0.798}$   
C=0.25

$t_c$ (min)	(mm/hr)	$Q_5$ (m <sup>3</sup> /s)	$Q_{stored}$ (m <sup>3</sup> /s)	Peak Volume (m <sup>3</sup> )
1	257.457	0.987	0.850	51.012
2	222.596	0.854	0.717	85.984
3	196.832	0.755	0.618	111.193
4	176.936	0.678	0.541	129.949
5	161.064	0.618	0.481	144.177
6	148.075	0.568	0.431	155.083
7	137.231	0.526	0.389	163.466
8	128.025	0.491	0.354	169.875
9	120.104	0.461	0.324	174.707
10	113.207	0.434	0.297	178.251
11	107.143	0.411	0.274	180.729
12	101.764	0.390	0.253	182.311
13	96.958	0.372	0.235	183.129
14	92.635	0.355	0.218	183.291 ***
15	88.723	0.340	0.203	182.884
16	85.165	0.327	0.190	181.978
17	81.913	0.314	0.177	180.632
18	78.928	0.303	0.166	178.896
19	76.177	0.292	0.155	176.810
20	73.633	0.282	0.145	174.411
21	71.273	0.273	0.136	171.730
22	69.077	0.265	0.128	168.792
23	67.028	0.257	0.120	165.620
24	65.110	0.250	0.113	162.234
25	63.312	0.243	0.106	158.652
26	61.623	0.236	0.099	154.890
27	60.031	0.230	0.093	150.961
28	58.529	0.224	0.087	146.878
29	57.110	0.219	0.082	142.651

Table 5.2.4



On-Site Storage

Calculator

Calculator

Town of Nemarket 25-Year

Project: Residential

Development

Project No.: 99-598

By: IS

Date: 19-Feb-21

Location: **Eagle street between Dixon Blvd abd Donlin Ave.**

A =	2.0300 ha	
Composite C =	0.7480	$i_{25} = 1100 * (T+2.0)^{-0.776}$
$i_{25}$ (Allowable) =	159.94 mm/hr	C=0.25
$Q_{Allowable}$ =	0.2255 m <sup>3</sup> /s	The proposed runoff coefficient has been
$Q_{Actual}$ =	0.1930 m <sup>3</sup> /s	increased as per MTO Design Chart 1.07

$t_c$ (min)	(mm/hr)	$Q_{25}$ (m <sup>3</sup> /s)	$Q_{stored}$ (m <sup>3</sup> /s)	Peak Volume (m <sup>3</sup> )
1	468.972	1.978	1.785	107.104
2	375.141	1.582	1.389	166.716
3	315.495	1.331	1.138	204.790
4	273.872	1.155	0.962	230.919
5	242.995	1.025	0.832	249.577
6	219.076	0.924	0.731	263.174
7	199.940	0.843	0.650	273.137
8	184.244	0.777	0.584	280.377
9	171.109	0.722	0.529	285.507
10	159.937	0.675	0.482	288.957
11	150.305	0.634	0.441	291.039
12	141.905	0.599	0.406	291.988 ***
13	134.507	0.567	0.374	291.983
14	127.937	0.540	0.347	291.164
15	122.057	0.515	0.322	289.642
16	116.762	0.492	0.299	287.509
17	111.964	0.472	0.279	284.838
18	107.595	0.454	0.261	281.691
19	103.598	0.437	0.244	278.119
20	99.925	0.421	0.228	274.165
21	96.537	0.407	0.214	269.867
22	93.400	0.394	0.201	265.257
23	90.488	0.382	0.189	260.363
24	87.776	0.370	0.177	255.207
25	85.242	0.360	0.167	249.813
26	82.870	0.350	0.157	244.198
27	80.644	0.340	0.147	238.379
28	78.550	0.331	0.138	232.370
29	76.577	0.323	0.130	226.185

Table 5.2.5



On-Site Storage  
Calculator

Project: Residential  
Development  
Project No.: 99-598  
By: IS  
Date: 19-Feb-21

**Town of Nemarket 50-Year**

Location: **Eagle street between Dixon Blvd abd Donlin Ave.**

A =	2.0300 ha	
Composite C =	0.8160	$i_{50} = 1488 * (T+3.0)^{-0.803}$
$i_{50}$ (Allowable) =	0.23 mm/hr	C=0.25
$Q_{Allowable}$ =	0.0003 m <sup>3</sup> /s	The proposed runoff coefficient has been
$Q_{Actual}$ =	0.2674 m <sup>3</sup> /s	increased as per MTO Design Chart 1.07

$t_c$ (min)	(mm/hr)	$Q_{50}$ (m <sup>3</sup> /s)	$Q_{stored}$ (m <sup>3</sup> /s)	Peak Volume (m <sup>3</sup> )
1	488.820	2.249	1.982	118.909
2	408.630	1.880	1.613	193.541
3	352.978	1.624	1.357	244.218
4	311.881	1.435	1.168	280.241
5	280.170	1.289	1.022	306.527
6	254.886	1.173	0.905	325.950
7	234.209	1.078	0.810	340.314
8	216.952	0.998	0.731	350.818
9	202.311	0.931	0.664	358.291
10	189.717	0.873	0.606	363.331
11	178.757	0.823	0.555	366.378
12	169.123	0.778	0.511	367.768 ***
13	160.581	0.739	0.471	367.760
14	152.951	0.704	0.436	366.558
15	146.090	0.672	0.405	364.326
16	139.883	0.644	0.376	361.197
17	134.238	0.618	0.350	357.280
18	129.081	0.594	0.327	352.666
19	124.348	0.572	0.305	347.432
20	119.987	0.552	0.285	341.642
21	115.956	0.534	0.266	335.352
22	112.217	0.516	0.249	328.609
23	108.737	0.500	0.233	321.454
24	105.492	0.485	0.218	313.923
25	102.455	0.471	0.204	306.047
26	99.609	0.458	0.191	297.855
27	96.934	0.446	0.179	289.371
28	94.415	0.434	0.167	280.616
29	92.038	0.423	0.156	271.610

Table 5.2.6



On-Site Storage  
Calculator

Project: Residential  
Development  
Project No.: 99-598  
By: IS  
Date: 19-Feb-21

**Town of Nemarket 100-Year**

Location: **Eagle street between Dixon Blvd abd Donlin Ave.**

$A = 2.0300$  ha  
**Composite C = 0.8500**  
 $i_{100 (Allowable)} = 203.31$  mm/hr  
 $Q_{Allowable} = 0.2866$  m<sup>3</sup>/s  
 $Q_{Actual} = 0.2460$  m<sup>3</sup>/s

$i_{100} = 1770 * (T+4.0)^{-0.82}$   
 $C=0.25$   
 The proposed runoff coefficient has been increased as per MTO Design Chart 1.07

$t_c$ (min)	(mm/hr)	$Q_{100}$ (m <sup>3</sup> /s)	$Q_{stored}$ (m <sup>3</sup> /s)	Peak Volume (m <sup>3</sup> )
1	472.953	2.267	2.021	121.253
2	407.276	1.952	1.706	204.732
3	358.916	1.720	1.474	265.375
4	321.691	1.542	1.296	311.012
5	292.075	1.400	1.154	346.180
6	267.900	1.284	1.038	373.702
7	247.760	1.188	0.942	395.442
8	230.698	1.106	0.860	412.680
9	216.043	1.036	0.790	426.333
10	203.305	0.974	0.728	437.072
11	192.123	0.921	0.675	445.404
12	182.220	0.873	0.627	451.720
13	173.382	0.831	0.585	456.325
14	165.444	0.793	0.547	459.463
15	158.269	0.759	0.513	461.332
16	151.750	0.727	0.481	462.092 ***
17	145.799	0.699	0.453	461.877
18	140.342	0.673	0.427	460.799
19	135.318	0.649	0.403	458.950
20	130.677	0.626	0.380	456.412
21	126.375	0.606	0.360	453.252
22	122.376	0.587	0.341	449.531
23	118.647	0.569	0.323	445.297
24	115.161	0.552	0.306	440.598
25	111.894	0.536	0.290	435.471
26	108.826	0.522	0.276	429.952
27	105.939	0.508	0.262	424.071
28	103.217	0.495	0.249	417.856
29	100.645	0.482	0.236	411.330



# Determining Number of Cartridges for Flow Based Systems

Date

8/13/2020

Black Cells = Calculation

## Site Information

Project Name

Eagle Street Residential Development

Project Location

Newmarket, ON

OGS ID

Stormfilter

Drainage Area, Ad

5.01 ac (2.03 ha)

Impervious Area, Ai

3.46 ac

Pervious Area, Ap

1.55

% Impervious

69%

Runoff Coefficient, Rc

0.70

Treatment storm flow rate, Q<sub>treat</sub>

1.81 cfs (51.2 L/s)

Peak storm flow rate, Q<sub>peak</sub>

8.72 cfs (247 L/s)

## Filter System

Filtration brand

StormFilter

Cartridge height

27 in

Specific Flow Rate

1.67 gpm/ft<sup>2</sup>

Flow rate per cartridge

18.79 gpm

## SUMMARY

Number of Cartridges

44

Media Type

Perlite

Event Mean Concentration (EMC)

120 mg/L

Annual TSS Removal

80%

Percent Runoff Capture

90%



Recommend SFPD 0822

200 Enterprise Drive  
Scarborough, ME 04074  
Phone 877-907-8676  
Fax 207-885-9825


## STORMFILTER DESIGN TABLE

- THE 8' x 22' PEAK DIVERSION STORMFILTER TREATMENT CAPACITY VARIES BY CARTRIDGE COUNT AND LOCALLY APPROVED SURFACE AREA SPECIFIC FLOW RATE. PEAK CONVEYANCE CAPACITY TO BE DETERMINED BY ENGINEER OF RECORD.
- THE PEAK DIVERSION STORMFILTER IS AVAILABLE IN A LEFT INLET (AS SHOWN) OR RIGHT INLET CONFIGURATION.
- ALL PARTS AND INTERNAL ASSEMBLY PROVIDED BY CONTECH UNLESS OTHERWISE NOTED.

CARTRIDGE HEIGHT	27"		18"		LOW DROP	
SYSTEM HYDRAULIC DROP (H - REQ'D. MIN.)	3.05'		2.3'		1.8'	
HEIGHT OF WEIR (W)	3.00'		2.25'		1.75'	
TREATMENT BY MEDIA SURFACE AREA	2 gpm/ft <sup>2</sup>	1 gpm/ft <sup>2</sup>	2 gpm/ft <sup>2</sup>	1 gpm/ft <sup>2</sup>	2 gpm/ft <sup>2</sup>	1 gpm/ft <sup>2</sup>
CARTRIDGE FLOW RATE (gpm)	22.5	11.25	15	7.5	10	5



SITE SPECIFIC DATA REQUIREMENTS			
STRUCTURE ID	*		
WATER QUALITY FLOW RATE (cfs)	*		
PEAK FLOW RATE (cfs)	*		
RETURN PERIOD OF PEAK FLOW (yrs)	*		
# OF CARTRIDGES REQUIRED	*		
CARTRIDGE FLOW RATE	*		
MEDIA TYPE (CSF, PERLITE, ZPG)	*		
PIPE DATA:	I.E.	MATERIAL	DIAMETER
INLET PIPE	*	*	*
OUTLET PIPE	*	*	*
INLET BAY RIM ELEVATION	*		
FILTER BAY RIM ELEVATION	*		
ANTI-FLOTATION BALLAST	WIDTH	HEIGHT	
	*	*	
NOTES/SPECIAL REQUIREMENTS:			



**PERFORMANCE SPECIFICATION**  
 FILTER CARTRIDGES SHALL BE MEDIA-FILLED, PASSIVE, SIPHON ACTUATED, RADIAL FLOW, AND SELF CLEANING. **RADIAL MEDIA DEPTH SHALL BE 7-INCHES**. FILTER MEDIA CONTACT TIME SHALL BE AT LEAST **37 SECONDS**.  
 SPECIFIC FLOW RATE SHALL BE **2 GPM/SF (MAXIMUM)**. SPECIFIC FLOW RATE IS THE MEASURE OF THE FLOW (GPM) DIVIDED BY THE MEDIA SURFACE CONTACT AREA (SF). MEDIA VOLUMETRIC FLOW RATE SHALL BE **6 GPM/CF OF MEDIA (MAXIMUM)**.

- GENERAL NOTES**
1. CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
  2. DIMENSIONS MARKED WITH ( ) ARE REFERENCE DIMENSIONS. ACTUAL DIMENSIONS MAY VARY.
  3. FOR FABRICATION DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHTS, PLEASE CONTACT YOUR CONTECH REPRESENTATIVE. [www.contechES.com](http://www.contechES.com)
  4. STORMFILTER WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF PROJECT.
  5. STRUCTURE SHALL MEET AASHTO HS20 LOAD RATING, ASSUMING EARTH COVER OF 0' - 5' AND GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. CASTINGS SHALL MEET AASHTO M306 AND BE CAST WITH THE CONTECH LOGO.

- INSTALLATION NOTES**
- A. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
  - B. CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STORMFILTER STRUCTURE (LIFTING CLUTCHES PROVIDED).
  - C. CONTRACTOR TO INSTALL JOINT SEALANT BETWEEN ALL SECTIONS AND ASSEMBLE STRUCTURE.
  - D. CONTRACTOR TO PROVIDE, INSTALL, AND GROUT PIPES. MATCH OUTLET PIPE INVERT WITH OUTLET BAY FLOOR.
  - E. CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT CARTRIDGES FROM CONSTRUCTION-RELATED EROSION RUNOFF.
  - F. CONTRACTOR TO REMOVE THE TRANSFER HOLE COVER WHEN THE SYSTEM IS BROUGHT ONLINE.



**CONTECH**  
 ENGINEERED SOLUTIONS LLC  
[www.contechES.com](http://www.contechES.com)  
 9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
 800-338-1122 513-645-7000 513-645-7993 FAX

THE STORMWATER MANAGEMENT STORMFILTER  
 8' x 22' PEAK DIVERSION STORMFILTER  
 STANDARD DETAIL

## **The Stormwater Management StormFilter<sup>®</sup> with PhosphoSorb<sup>®</sup> Media Performance Evaluation Study**

Phosphorus is a common cause of impairment in freshwater bodies throughout the United States. In urban watersheds, loads contributed by stormwater runoff can be a dominant source. As a result, phosphorus removal requirements are increasingly common and innovative phosphorus removal technologies are needed that can be integrated into an urban environment. Phosphosorb<sup>®</sup> (PhosphoSorb) is a proprietary phosphorus removal media comprised of a perlite base with activated alumina coating developed by Contech Engineered Solutions LLC (Contech) for use in media filtration systems.

A Stormwater Management StormFilter<sup>®</sup> (StormFilter) using PhosphoSorb media was evaluated for the removal of sediment and phosphorus over a 17 month period starting in February 2012. During this period a total of 19 qualified storm events were sampled according to a Quality Assurance Project Plan (Contech, 2012) designed to conform to the requirements given in Guidance for Evaluating Emerging Stormwater Treatment Technologies, Technology Assessment Protocol – Ecology (TAPE) (Ecology, 2011). The stormwater treatment system tested during this evaluation is a StormFilter containing one 18-inch tall StormFilter cartridge with PhosphoSorb media operating at a specific flow rate of 1.67 gpm/ft<sup>2</sup> or 12.5 gpm per cartridge (for an 18-inch cartridge).

The evaluation site is located on Lolo Pass Road at Bear Creek Bridge in ZigZag, Oregon. The 0.063 acre contributing drainage area upstream of the StormFilter catchment is 100% impervious and includes the bridge deck and adjacent roadway. Time of concentration ( $t_c$ ) on the site is estimated to be 1.4 minutes. A photo of the drainage area can be seen in Figure 1.



**Figure 1. View of the drainage area of the StormFilter evaluation site located on Lolo Pass Road, ZigZag, Oregon.**

Individual volume-paced influent and effluent samples were collected over the course of each qualified storm event using individual ISCO 6712 Portable Automated Samplers. Influent and effluent flows were measured using Large 60°V Trapezoidal Flumes in conjunction with individual ISCO 730 Bubbler Flow Modules. At the conclusion of each qualified runoff event, individual influent and effluent samples were combined to create influent and effluent bulk composite samples. Event Mean Concentration (EMC) subsamples were then taken from the bulk composite sample and submitted to Apex Laboratories, LLC in Beaverton, Oregon for analysis.



All 19 events had detectable influent concentrations for total phosphorus (TP), total suspended solids (TSS), and suspended solids concentration (SSC). Significant reductions in TP, TSS and SSC pollutant loads were observed between influent and effluent sampling locations. Performance was calculated using two different methods, the Efficiency Ratio (ER) method and the Summation of Loads (SOL) efficiency calculation method. The ER method defines the efficiency as the average event mean concentration of pollutants over a given time period.

$$ER = 1 - \frac{\text{mean effluent EMC}}{\text{mean influent EMC}}$$

The ER method assumes; 1) The weight of all storm events is equal regardless of the relative magnitude of the storm event and 2) that if all storm events at the site had been monitored, the average inlet and outlet EMCs would be similar to those that were monitored (URS/ EPA 1999). A summary of ER performance data for TP, TSS and SSC for the 19 sampled events is presented in Table 1.

**Table 1. Performance summary and Efficiency Ratios (ER) for the StormFilter with PhosphoSorb media for the 19 events sampled to date at the Lolo Pass Road evaluation site.**

Parameter	TSS (mg/L)		SSC (mg/L)		Total Phosphorus (mg/L)	
Analytical Method	SM 2540D		ASTM D3977		SM 4500PF	
Sample Location	Influent	Effluent	Influent	Effluent	Influent	Effluent
Min	40.0	6.00	46.0	7.59	0.068	0.0043
Max	780	120	1000	120	0.583	0.140
Median	360	27.0	404	25.7	0.170	0.0498
Mean	340	34.2	435	35.8	0.231	0.0580
<b>Efficiency Ratio</b>	<b>90%</b>		<b>92%</b>		<b>75%</b>	

The SOL method defines the efficiency as a percentage based on the ratio of the summation of all influent loads to the summation of all effluent loads.

$$SOL = 1 - \frac{\text{sum of all effluent loads}}{\text{sum of all influent loads}}$$

The SOL method assumes; 1) monitoring data accurately represents the actual entire total loads in and out of the BMP for a period long enough to overshadow any temporary storage or export of pollutants and 2) any significant storm events that were not monitored had a ratio of inlet to effluent loads similar to the storms events that were monitored (URS/ EPA 1999). SOL efficiency results for TP, TSS and SSC for the 19 sampled events is presented in Table 2.

**Table 2. Summation of Loads (SOL) efficiency calculations for the StormFilter with PhosphoSorb media for the 19 events sampled to date at the Lolo Pass Road evaluation site.**

Parameter	TSS (g)		SSC (g)		Total Phosphorus (mg)	
Analytical Method	SM 2540D		ASTM D3977		SM 4500PF	
Sample Location	Influent	Effluent	Influent	Effluent	Influent	Effluent
Total	43352	3577	54426	3691	33643	7228
<b>SOL Efficiency</b>	<b>92%</b>		<b>93%</b>		<b>79%</b>	

Particle size distribution information collected during sampled events confirms that the influent solids have a silt loam distribution which is typical for the Pacific Northwest and is comparable to other field evaluation studies. pH was also measured for all storm events using EPA Method 105.1. Median influent and effluent EMCs were 6.7 and 6.6 respectively.

Although testing is ongoing through the remainder of the 2013-2014 rain season, the 19 TAPE qualified events sampled to date provide a robust data set suitable for characterizing PhosphoSorb media performance. Data suggests that PhosphoSorb media can provide significant solids load reduction for both TSS and SSC as well as total phosphorus load reductions at or above levels dictated by stormwater permitting requirements and TMDL compliance plans.

**References**

Contech Engineered Solutions LLC. (Contech). (2012) Quality Assurance Project Plan: The Stormwater Management StormFilter, PhosphoSorb at a Specific Flow Rate 1.637 gpm/ft<sup>2</sup> Performance Evaluation. Portland, Oregon. (Revised September 2013).

URS Greiner Woodward Clyde, Urban Drainage and Flood Control District, Urban Water Resources Research Council (UWRRC) of ASCE, Office of Water, US Environmental Protection Agency (URS/EPA) (1999). Development of Performance Measures Task 3.1 – Technical Memorandum Determining Urban Stormwater Best Management Practice (BMP) Removal Efficiencies. Washington, D.C.

Washington State Department of Ecology (Ecology). (2011). Guidance for Evaluating Emerging Stormwater Treatment Technologies: Technology Assessment Protocol – Ecology (TAPE). Olympia, Washington.



## Project DEVELOPMENT Summary

**DEVELOPMENT:** Residential Development Eagle Street . Town of Newmarket  
**Subwatershed:** East Holland

Total Pre-Development Area (ha):	<b>2.03</b>	Total Pre-Development Phosphorus Load (kg/yr):	<b>0.26</b>
----------------------------------	-------------	--	-------------

Pre-Development Land Use	Area (ha)	P coeff. (kg/ha)	P Load (kg/yr)
Low Intensity Development	2.03	0.13	0.26

### POST-DEVELOPMENT LOAD

Post-Development Land Use	Area (ha)	P coeff. (kg/ha)	Best Management Practice applied with P Removal Efficiency	P Load (kg/yr)
Low Intensity Development	2.03	0.13	Other	80% 0.05

Post-Development Area Altered:	<b>2.03</b>		<b>P Load (kg/yr)</b>
Total Pre-Development Area:	<b>2.03</b>		
Unaffected Area:	<b>0</b>		
		Pre-Development:	<b>0.26</b>
		Post-Development:	<b>0.26</b>
		Change (Pre - Post):	<b>0.00</b>
		<b>0% Net Increase in Load</b>	
		Post-Development (with BMPs):	<b>0.05</b>
		Change (Pre - Post):	<b>0.21</b>
		<b>80% Net Reduction in Load</b>	

**CONSTRUCTION PHASE LOAD**

Site-Specific Input:		Constant / Lookup:	
		Calculation:	

Sub Area: Townhouses			
Duration of Construction (months):		R (rainfall / runoff for Lake Simcoe)	90
Duration of Exposed Soil (months):		K (soil erodability factor):	0.26
Surface Slope Gradient (%):		NN (determined by slope):	
Length of Slope (m):		BMP prevention Efficiency:	
Slope Area (ha):	2.03	BMP capture Efficiency:	
% slope erosion prevention applied to:		LS (slope length gradient factor):	
% slope runoff capture applied to:		C (portion of year of exposed soil):	
Subwatershed Soil [P] (kg/kg):		P (prevention + capture):	
		Soil Loss (kg/year):	
		Phosphorus Load (kg):	

**Developed AREA (ha):** 2.02999997139

**Total**

<b>Construction Phase Phosphorus Load with BMPs (kg):</b>
<b>Construction Phase Phosphorus Load no BMPs (kg):</b>

<b>SUMMARY WITH IMPLEMENTATION OF BMPs</b>	<b>P Load (kg/yr)</b>
Pre-Development:	<b>0.26</b>
Construction Phase Amortized Over 8 Years :	
Post-Development:	<b>0.05</b>
Post-Development + Amortized Construction:	
<b>Pre-Development Load - Post-Development Load:</b>	<b>0.21</b>
<b>Conclusion:</b>	<b>80% Reduction in Load</b>
<b>Pre-Development Load - (Post-Development + Amortized Construction Load):</b>	
<b>Conclusion:</b>	<b>% Reduction in Load</b>
<b>Based on a comparison of Pre-Development and Post-Development loads, and in consideration of Construction Phase loads, the Ministry would encourage the Municipality to:</b>	
<b>Approve development as site specific appropriate.</b>	

## **Appendix D**

Geotechnical Letter of Opinion, dated September 2020, prepared by Soil  
Engineers Ltd.  
Historical documents for western sanitary subtrunk



# Soil Engineers Ltd.

CONSULTING ENGINEERS

GEOTECHNICAL • ENVIRONMENTAL • HYDROGEOLOGICAL • BUILDING SCIENCE

90 WEST BEAVER CREEK ROAD, SUITE 100, RICHMOND HILL, ONTARIO L4B 1E7 · TEL: (416) 754-8515 · FAX: (905) 881-8335

**BARRIE**  
TEL: (705) 721-7863  
FAX: (705) 721-7864

**MISSISSAUGA**  
TEL: (905) 542-7605  
FAX: (905) 542-2769

**OSHAWA**  
TEL: (905) 440-2040  
FAX: (905) 725-1315

**NEWMARKET**  
TEL: (905) 853-0647  
FAX: (905) 881-8335

**GRAVENHURST**  
TEL: (705) 684-4242  
FAX: (705) 684-8522

**HAMILTON**  
TEL: (905) 777-7956  
FAX: (905) 542-2769

September 25, 2020

Reference No. 2009-S160

Page 1 of 2

Millford Development Limited  
P.O. Box 215  
Newmarket, Ontario  
L3Y 4X1

Attention: Mr. Frank Orsi

**Re: Geotechnical Letter of Opinion  
Proposed Townhouse Development  
55 Eagle Street  
Town of Newmarket**

Dear Sir:

Further to your request, we have reviewed the Functional Servicing and Stormwater Management Report (FSR) prepared by Masongsong Associates Engineering Limited together with the geotechnical investigation report, Reference No. 0409-S004 and offer the following opinion.

The geotechnical report revealed that beneath a topsoil/topsoil fill veneer or topsoil and earth fill layers, the site is underlain predominantly by strata of sandy silt till and silty clay. In places, strata of silty sand till, fine to coarse sand, silt or sandy silt and silty clay till were encountered. Groundwater was detected at depths ranging from 5.5 to 7.9 m from the ground surface.

A valley bank slope of a creek is located north of the property. Through a slope stability study, it was determined that the LSRCA staked top of bank can be considered the Long-Term Stable Top of Bank (LTSTOB) incorporating both the stable slope allowance and toe erosion allowance. A development setback of 6.0 m from the LTSTOB was recommended, which formed the development limit of the project.

A review of the FSR and associated engineering drawings show that all the elements of the proposed development fall behind the development limit except for a storm outlet which runs down to the creek at the northeast sector of the property. It is understood that this outlet will be properly designed during the design stage of the project.



The proposed townhouses typically would be founded on shallow spread and strip footings. The revealed native soil below the topsoil and earth fill is suitable for supporting the house footings. The existing earth fill can be upgraded to or replaced with engineered fill for foundation support.

A stormwater storage tank will be constructed near the northeast area of the development with the bottom of tank elevation at 255.20 m. Since the tank will be sitting at almost the same elevation as the bottom of the slope, it will not have any negative impact to the stability of the slope.

A grassed swale is proposed to run along the inside of the northern development limit. It is design to drain in a west and east direction. Provided that it does not channel the surface runoff to drain directly over the slope to the north, it should not have any negative impact to the stability of the slope.

Based on the above, it is our opinion that the proposed townhouse development as presented in the FSR and associated engineering drawings are geotechnically suitable.

We trust this meets your present requirements. Should you have any queries, please feel free to contact the undersigned.

Yours very truly,  
**SOIL ENGINEERS LTD.**

Bernard Lee, P.Eng.  
BL:dd



c. Soil Engineers Ltd. (Newmarket)  
Mr. Stephen Lee, Branch manager

This letter/report/certification was prepared by Soil Engineers Ltd. for the account of the captioned clients and may be relied upon by regulatory agencies. The material in it reflects the writer's best judgment in light of the information available to it at the time of preparation. Any use which a third party makes of this letter/report/certification, or any reliance on or decisions to be made based upon it, are the responsibility of such third parties. Soil Engineers Ltd. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this letter/report/certification.

TOWN OF NEWMARKET


# WATER AND WASTEWATER MASTER PLAN

MASTER PLAN REPORT

MARCH 2017







**Legend**

- Manholes
- Sanitary Sewers
- Waterbodies
- Watercourses
- Parcels
- Railway
- York Region Sanitary Sewer
- Land Use**
- ICI
- Residential
- Open Space


**Alternatives**

- Alternative 1 - Upgrade Holland River Trunk Sewer
- Alternative 2 - New In-line storage sewer on Cane Parkway
- Alternative 3 - New sewer on Cane Parkway, Mullock Drive and rail corridor to YDSS



Project No. 151-04561-00


**Newmarket Water and Wastewater Master Plan**




**Figure 6.7**

**Wastewater Alternatives for Servicing Holland River Trunk Sewer**

# Western Sub-Trunk





**Legend**

- Regional Pumping Station
- Town Pumping Station
- YDSS Forcemain
- Town Forcemain
- YDSS Sanitary Sewer
- Sanitary Sewers
- Trunk Sewers
- Municipal Boundary
- Waterbodies
- Watercourses
- Parcels
- Railway

**Land Use**

- ICI
- Residential
- Open Space



Project No. 151-04561-00

**Newmarket Water and Wastewater Master Plan**




Figure 6.1

**Town of Newmarket Existing Wastewater System**

May 2, 1984

G.M. Sernas & Associates Ltd.  
85 The East Mall  
Suite 111  
Toronto, Ontario M8Z 5W4

Attention: Mr. V.J. Gupta, P.Eng.

Dear Sir:

RE: Sanitary Drainage for Orsi Lands  
Yonge and Eagle Streets  
Town of Newmarket

Thank you for the transmittal of April 26th with the sanitary sewer design sheet for the outfall from Yonge Street across the Orsi lands east of Yonge Street. I note that your design sheet shows 28.0 ha. of apartment lands draining to the sanitary sewer, apparently from the Orsi lands, and an equivalent estimated 1,719 persons, totalling  $.0406 \text{ m}^3/\text{sec.}$ , or 1.43 cfs. Your letter of April 10th indicates that this 28 ha. is from the Orsi lands west of Yonge Street and 3.6 ha. is from the Orsi lands east of Yonge Street, and this is satisfactory.

In explanation of this current letter, the new proposals by the Town and the Region for a recreation complex, administration centre, and as we understand it, a land exchange with Glenway, apparently initiated certain changes to the design capacity of this sewer, and we were advised that we would receive new design information, which you have now forwarded to us.

I am still not certain as to what is intended, but as I understand your design sheet and your letter of April 10th, there is a sewage flow allowed from the Orsi lands of  $.0453 \text{ m}^3/\text{sec.}$ , and providing that this capacity is reserved for the Orsi lands, I believe that my clients are satisfied.

The Orsi's have already given permission for the tunnel contractor to enter onto their property, and I believe that they are satisfied to allow the sewer contractor to do the same, but he should double check that with them. The Orsi's had no intention of delaying the permission, and certainly did not want to penalize the contractor, but did feel that if they were going to give a contractor permission to work on their property to

.../pg 2

Mr. V.J. Gupta, P.Eng.  
May 2, 1984

Page 2.

install a sanitary sewer, that they should at least be able to satisfy themselves that the sewer had enough capacity for their properties. It is in this context that they now give permission to the contractor to work on their property, and with the understanding that the sewer capacity as indicated on your design sheet is allocated to them, and that it is satisfactory to the Town of Newmarket.

We understand that your sewer design has been approved by the Town, and that this allocation is now acceptable to the Town. We quite understand that this does not have any relation to planning decisions or allocation for sewage treatment, but simply establishes a sewer capacity in the particular sewers that you have designed.

We also understand that the contractor agrees to restore the Orsi lands to equal or better condition than before he entered the site, and I believe that he has given the Orsi's a letter directly to confirm this.

Yours truly,

PATRICK FALBY & ASSOCIATES LTD.



P.R. Falby, P.Eng.  
Consulting Engineer

CC: Mr. & Mrs. F. Orsi ✓  
: Mr. R. Howard, Town Engineer  
: Mr. D. Brierley, P.Eng.

CONSULTING  
PROFESSIONAL  
ENGINEERS



G.M. SERNAS, M.A.Sc., P.ENG.  
R.D. WEBSTER, B.ENG., P.ENG.  
O.B. CARLSON, C.E.T.  
A.B. SERGAUTIS, B.A.Sc., P.ENG.

G. M. SERNAS & ASSOCIATES LTD.

HEAD OFFICE:  
85 THE EAST MALL, SUITE 111  
TORONTO, ONTARIO M8Z 5W4  
TELEPHONE (416) 259-6323  
TELEX NO.: 06-986766 TOR

165 BROCK ST. NORTH, SUITE 207  
WHITBY, ONTARIO L1N 4H3  
TELEPHONE (416) 668-0764

April 10, 1984

RUSH COURIER

Patrick Falby & Associates Ltd.  
377 Sweetwater Crescent  
Mississauga, Ontario  
L5H 4A7

Attention: Mr. P. Falby

Dear Sir:

RE: SANITARY DRAINAGE FOR ORSI LANDS  
YONGE AND EAGLE STREETS  
TOWN OF NEWMARKET

Further to your letter of March 15th, 1984, to Delcan, please note that the sanitary sewer design across Yonge Street and the Orsi lands, allows for the expected sewage from twenty-eight hectares of land owned by Mr. and Mrs. Orsi west of Yonge Street, and 3.6 hectares of land owned by Mr. and Mrs. Orsi east of Yonge Street, in addition to the expected sewage from Glenway Estates & Country Club and the Regional lands. We understand that you concur with the following expected sewage flows from the Orsi lands indicated on our sanitary sewer design sheets:

28 hectares	0.0406 cubic meters per second
3.6 hectares	0.0047 cubic meters per second

Please also note that the above flows were developed based on the latest land use information obtained from the Planning Department of the Town of Newmarket.

We appreciate your confirmation to Delcan in the above-mentioned letter that you have no problem with our design servicing

Patrick Falby & Associates Ltd.  
Attn: Mr. P. Falby

G. M. SERNAS & ASSOCIATES LTD.


April 10, 1984

Page 2

the Orsi lands.

Yours very truly,

G. M. SERNAS & ASSOCIATES LTD.



Vijay Gupta, P.Eng.

VG:mjg

cc: Delcan, Attn: Mr. D. Brierley, P.Eng. (Rush Courier)  
Town of Newmarket, Attn: Mr. R. E. Howard, P.Eng., Town Engineer  
(Overnight Courier)  
Mr. and Mrs. Orsi (Overnight Courier)



# Town of Newmarket

OFFICE OF THE ENGINEER

BOX 328 - 171 MAIN STREET  
NEWMARKET, ONTARIO  
L3Y 4X7

HEART OF THE REGION OF YORK

Patrick Falby & Associates Ltd.  
Consulting Engineers  
877 Sweetwater Crescent  
MISSISSAUGA, Ontario  
L5H 4A7

1983 12 22

Dear Sirs:

RE: Orsi Properties  
East & West Sides of Yonge St.  
At Eagle Street

I acknowledge receipt of your letter of December 10th, 1983 regarding the Report of G.M. Sernas & Associates Ltd. dealing with the Western Sanitary Subtrunk Sewer.

I confirm my telephone advice to you that G.M. Sernas is presently addressing the second draft comments of our Checking Consultant, DeLCan.

For a study and report of the magnitude and importance of the aforementioned Western Sanitary Subtrunk Study, it will be necessary for the Town Engineer to clear the report through the Mayor's Industry and Subdivision Committee and obtain permission, at that time, to release the report. Any variance to this procedure which you may wish to request, in the interests of speed, must be processed through the Mayor's Office.

We trust that this information is useful to you at this time and would recommend that you contact this office from time to time in order to determine the status of the Report.

Yours very truly,

R.E. Howard, P. Eng.  
Town Engineer

REH:cs

c.c. Mayor R. Twinney  
R.N. Shelton, P. Eng., Deputy Town Engineer  
D.J. Brierley, P. Eng., DeLCan